SPECIAL NOTES

1 The Contractor is required to check the numbers of the pages and should any be found to be missing or in duplicate or the figures or writing indistinct, they must inform the Quantity Surveyors at once and have the same rectified. Should the Contractor be in doubt about the precise meaning of any item, word or figure, for any reason whatsoever, or observe any apparent omission of words or figures they must inform the Quantity Surveyor in order that the correct meaning may be decided upon before the date for the submission of the Tender.

2 No liability whatever will be admitted nor claim allowed in respect of errors in the Contractor's Tender due to mistakes in the Bills of Quantities which should have been rectified in the manner described above.

3 Any doubt or obscurity as to the meaning or intention of any part of the tender documents, or any question arising, shall be taken up in writing, before submission of the tender so that the same can be clarified.

4 The Contractor shall not alter or otherwise qualify the text of these Bills of Quantities. Any alteration or qualification made without authority will be ignored and the text of the Bills of Quantities as printed will be adhered to.

5 The Contractor shall be deemed to have made allowance in their prices generally to cover items of Preliminaries or additions to Prime Cost Sums or other items, if these have not been priced against the respective items.

6 All items of measured work shall be priced in detail and tenders containing lump sums to cover trades or groups of work must be broken down to show prices for each item before they will be accepted. Lump sums to cover items of Preliminaries shall likewise be broken down if so required.

7 In no case will any expenses incurred by Contractors in preparation of this Tender be reimbursed.

8 The copyright of these Bills of Quantities is vested in the Quantity Surveyors and no part thereof may be reproduced without their express permission given in writing.

9 The Contractor is solely responsible for the accurate ordering of materials in accordance with the Drawings and Architect's instructions and no claims for any loss or expense will be entertained for orders for materials based upon the Bills of Quantities.

10 The Bills of Quantities must be priced in Kenya Shillings (KES) and cents currency. i.e., KES & cents.

11 The tender documents must be priced in ink.

USD TO KSH 130.00

INDEX

SECTION NO. 1	PRELIMINARIES AND GENERAL DESCRIPTION OF MATERIALS AND WORKMANSHIP
SECTION NO. 2	MAIN BUILDING
SECTION NO. 3	SEPTIC TANK
SECTION NO. 4	VISA AND PASSPORT OFFICE
SECTION NO. 5	BOUNDARY WALL
SECTION NO. 6	GUARD ROOM
SECTION NO. 7	GENERATOR ROOM
GRAND SUMMARY	BUDGET SUMMURY

ITEM	GRANT NO. IOMGRW00	
	SECTION NO. 1	
	PRELIMINARIES	
	PRELIMINARY PARTICULARS	
A	**PARTIES**	
	The "Employer" is **Centum Investment Company**	
	For the purpose of the works which are under the control of the consultants above, the respective consultants shall be deemed to be invested with the duties and be representatives of the Architect.	
B	**SITE**	
	The site is located on NAKURU COUNTY	
	The site of the works shall be used solely for the purpose of executing and completing the Contract to the satisfaction of the Architect.	
	The Contractor shall obtain the engineer's approval for the siting of all temporary storage areas for materials.	
	The Contractors shall visit the site to acquaint themselves with its nature and position, the nature of the ground, sub- strata and other local conditions, position of power and water supplies, access roads or any other limitations, and no claims for extras will be considered on account of lack of knowledge in this respect.	
	The Contractor's attention is drawn to the fact that they shall confine themselves to the area necessary for executing the works as instructed by the Engineer.	
	The contractor must obtain the engineer's approval and directions regarding the use of any materials found on the Site. Any such material utilized in the execution of the Contract shall be measured and value assessed by the Quantity Surveyor and the amount credited to the Employer.	
	Carried To Collection **KSH**	**-**

	GENERAL MATTERS	
A	**SUFFICIENCY OF TENDER**	
	The Contractor shall be deemed to have satisfied themselves before tendering as to the correctness and sufficiency of their Tender for the Works and of the rates and prices stated in the priced Bills of Quantities, which rates and prices shall cover all their obligations under the Contract and all matters and things necessary for the proper completion and maintenance of the Works.	
B	**STAMP CHARGES**	
	The Contractor shall allow for the payment of all Stamp Charges in connection with the Surety Bond and Contract Agreement.	10,400.00
C	**DEFINITIONS AND ABBREVIATIONS**	
	Terms used in these Bills of Quantities shall be interpreted as follows:	
	"Approved" shall mean approved by the Architect.	
	"as directed" shall mean as directed by the Architect or any other consultant in the contract.	
	"BS" Shall mean the current British Standard Specification published by the British Standards Institution, 2 Park Street, London W.1, England.	
	"CM" shall mean Cubic Meters.	
	"SM" shall mean Square Meters.	
	"LM" shall mean Linear Meters.	
	"mm" shall mean Millimeters.	
	"Kg" shall mean Kilograms.	
	"No." shall mean Number.	
	"m.s" shall mean Measured separately.	
	"Ditto " shall mean as described before or as above described.	
D	**PROGRESS SCHEDULE**	
	The Contractor shall, upon receiving instructions to proceed with the work, draw up a Time and Progress Schedule setting out the order in which the Works are to be carried out with the appropriate dates thereof. This Time and Progress Schedule is to be agreed with the Architect and no deviation from the order set out in this Schedule will be permitted without the written consent of the Architect. The Main Contractor will be responsible for arranging the above programme with all Sub-Contractors including the Nominated Sub-Contractors and Nominated Suppliers.	5,200.00
E	**FIGURED DIMENSIONS**	
	Figured dimensions are to be followed in preference to dimensions scaled from the Drawings; but whenever possible dimensions are to be taken on the Site or from the Buildings. Before any work is commenced by Sub-Contractors or Specialist Firms, dimensions must be checked on the Site and/or buildings and agreed with the Contractor, irrespective of the comparable dimensions shown on the Drawings. The Contractor shall be responsible for the accuracy of such dimensions.	
	Carried To Collection **KSH**	**15,600.00**

A	**PROVISIONAL WORK** All "provisional" and other work liable to adjustment under this Contract shall be left uncovered for a reasonable time to allow all measurements needed for such adjustment to be taken by the Quantity Surveyor. Immediately the work is ready for measurement, the Contractor shall give notice to the Quantity Surveyor. If the Contractor makes default in these respects he shall, if the Architect so directs, uncover the work at his own expense to enable the measurements to be taken.	
B	**EXISTING SERVICES** Prior to commencement of any work the Contractor is to ascertain from the relevant Authorities the exact position, depth and level of all existing electric cables, water pipes or other services in the area and they shall make whatever provisions may be required by the Authorities concerned for the support and protection of such services. Any damage or disturbance caused to any services shall be reported immediately to the Architect and the relevant Authority and shall be made good to their satisfaction at the Contractor's expense.	
C	**TRANSPORT TO AND FROM THE SITE** The Contractor shall include in their prices for the transport of materials, workmen, etc., to and from the Site of the proposed Works, at such hours and by such routes as are permitted by the Authorities.	19,500.00
D	**OVERTIME** The Contractor shall allow in their tender for any extra costs for overtime working they consider will be necessary in order to complete the works by the contract Date of Completion. If during the course of the Contract overtime is worked for a specific purpose in accordance with a written instruction issued by the Architect, the Contractor will be reimbursed in respect of such overtime to the extent only of the additional net cost of unproductive time payable over and above the basic hourly rates as laid down by the Regulations of Wages and Conditions of Employment Act, Building and Construction Industry Wages council and excluding any bonuses, profits and overheads.	
E	**PUBLIC AND PRIVATE ROADS, PAVEMENTS, ETC.** The Contractor will be required to make good, at their own expense, any damage they may cause to the present road surfaces and pavements within or beyond the boundary of the Site, during the period of the Works. In particular, all existing trees, shrubs, plants, etc., which may be destroyed or damaged during the progress of the Works are to be made good by the Contractor to the approval of the Architect.	
F	**POLICE REGULATIONS** The Contractor is to allow for complying with all instructions and regulations of the Police Authorities.	6,500.00
	Carried To Collection **KSH**	**26,000.00**

A	**CONTRACTORS' SUPERINTENDENCE**	
	The Contractor shall constantly keep on the Works a literate English-speaking Agent or Representative, competent and experienced in the kind of work involved, who shall give his whole time to the superintendence of the Works. Such Agent or Representative shall receive on behalf of the Contractor, directions and instructions from the Architect and such directions and instructions shall be deemed given to the Contractor in accordance with the Conditions of Contract. The Agent shall not be replaced without the specific approval of the Architect.	
	It is to be a specific condition of this Contract that the successful Tenderer shall provide on site throughout the period from the completion of the substructure to the Date for Practical Completion a suitably qualified, experienced and competent person to ensure that the works are carried out to the standard required by the specification and detailed on the Drawings; and shall ensure that upon any termination of employment a suitable replacement is found.	
	Before the Tenderer's offer is accepted the Architect will personally interview the Contractor's proposed Representative. A curriculum vitae of past experience and qualifications must be provided for the Architect's scrutiny.	
	The Architect's decision will be final regarding the suitability of the proposed Representative.	65,000.00
B	**WATER**	
	All water shall be fresh, clean and pure, free from earthy vegetable or organic matter, acid or alkaline substance in solution or suspension.	
	The Contractor shall provide at their own risk and cost all water for use in connection with the Works (including the work of Sub-Contractors). The Contractor shall provide at their own expense all temporary distribution pipes, storage tanks, meters, etc., and they shall clear away same upon completion of the Works.	6,500.00
C	**LIGHTING AND POWER**	
	The Contractor shall provide at their own risk and cost all artificial lighting and power for use on the Works, including all Sub-Contractors' and Specialists' requirements and including all temporary connections, wiring, fittings, etc., and clearing away on completion. The Contractor shall pay all fees and obtain all permits in connection therewith.	45,500.00
D	**SAFETY**	
	In particular there shall be proper provision of planked footways and guard-rails to scaffolding, etc.; protection against falling materials and tools and the Site shall be kept tidy and clear of dangerous rubbish.	10,400.00
	The Architect shall be empowered to suspend work on the Site should he consider these conditions are not being observed, and no claim arising from such a suspension will be allowed.	
	Carried To Collection **KSH**	**127,400.00**

A	**PROTECTIVE CLOTHING**	
	The Contractor shall provide all protective or any other special clothing or equipment for their employees that may be necessary.	
	These shall include, inter-alia, safety helmets, gloves, goggles, earmuffs, gumboots, steel toed boots, overalls, etc according to the type of work. The Contractor shall ensure that all safety and protective gear are worn by all staff on site at all times	10,400.00
	MATERIALS AND WORKMANSHIP	
B	**GENERALLY**	
	All materials shall be new unless otherwise directed or permitted by the Architect and in all cases where the quality of goods or materials is not described or otherwise specified, is to be the best quality obtainable in the ordinary meaning of the word "best" and not merely a trade signification of that word.	
	All materials and workmanship shall, unless otherwise specified or described, conform to the appropriate Kenya Bureau of Standards or British Standards Institution Specification current at the date of tender.	
	The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also order materials to be obtained from local sources as early as necessary to ensure that such materials are on Site when required for use in the Works.	
	The Contractor shall be responsible for and shall replace or make good at their own expense any materials lost or damaged.	
	The Works throughout shall be executed by skilled workmen well versed in their respective trades.	
C	**REJECTED WORKMANSHIP OR MATERIALS**	
	Any workmanship or materials not complying with the specific requirements or approved samples or which have been damaged, contaminated or have deteriorated, must immediately be removed from the Site and replaced at the Contractor's expense, as required.	
D	**PROPRIETARY MATERIALS**	
	Where proprietary materials are specified herein-after the Contractor may propose the use of materials of other manufacture but equal quality for approval by the Architect.	
	All materials and goods, where specified to be obtained from a particular manufacturer or supplier are to be used or fixed strictly in accordance with their instructions.	
E	**SAMPLES**	
	The Contractor shall furnish at the earliest possible opportunity before work commences and at his own cost, any samples of materials or workman-ship that may be called for by the Architect for his approval or rejection, and any further samples in the case of rejection until such samples are approved by the Architect and such samples, when approved, shall be the minimum standard for the work to which they apply.	32,500.00
	Carried To Collection KSH	**42,900.00**

A	**CONCRETE TESTS**	
	Concrete test cubes I.e. per set of three as later described, including testing fees, labour and materials, making moulds, transport and handling etc.. and ensuing copies of tests are promptly dispatched to the Architect's and Quantity Surveyor's offices. Successful tests only (Provisional)	10,400.00
	TEMPORARY WORKS	
B	**SPACE AND SERVICES FOR THE ARCHITECT**	
	The Contractor shall provide where directed within the site, site offices and clean toilet facilities for the sole use of the Architect and their representatives to the satisfaction of the Local Authorities. The offices shall be provided with adequate furniture and the contractor shall provide the services of a sweeper, pay all charges and keep the facilities in a clean and sanitary condition during the whole period of the Works. In particular, the Contractor is to note that the station will continue with operations during the period of the works and a separate office and store shall be provided for full time use by the station dealer. Equally, separate sanitary amenities shall be provided for the station staff to the satisfaction of the Architect and local authorities.	7,800.00
C	**TELEPHONE**	
	The Contractor shall provide a telephone connection to the town exchange for the period of the Works, and shall pay all fees and rental for the same. The telephone connection shall remain on site until completion of the works.	
D	**SANITATION**	
	The Contractor shall make arrangements for the necessary toilet facilities for their staff and workmen to the requirements and satisfaction of the Health authorities and maintain the same in a thoroughly clean and sanitary condition and pay all conservancy fees during the period of the Works and remove when no longer required.	3,900.00
E	**PLANT, TOOLS AND SCAFFOLDING**	
	The Contractor shall provide all necessary hoists, tackle, plant, vehicles, tools and appliances of on every description for the due and satisfactory completion of the Works and shall remove same completion.	
	The Contractor shall provide, erect and maintain all temporary scaffolding, sufficiently strong and efficient for the due performance of the Works, including Sub-contract Works, provide special scaffolding as and when required during the Works and remove on completion and make good.	
	Such scaffolding shall be constructed of tubular steel or timber of sufficient scantlings and be provided with planked footways and guard-rails to approval.	
	All such plant, tools and scaffolding shall comply with all regulations whether general or local, in force throughout the period of the Contract and shall be altered or adapted during the Contract as may be necessary to comply with any amendments in or additions to such regulations.	
	Scaffolding is not measured hereinafter, and the Contractor must allow here or in his rates for the above.	65,000.00
	Carried To Collection KSH	**87,100.00**

A	**EXISTING AND ADJACENT PROPERTY** The Contractor must take all steps necessary to safeguard existing and adjacent property, make good at their own expense any damage to persons or property caused thereon, and hold the Employer indemnified against any such claim arising. The Contractor will be held fully responsible for the safety of the existing and adjacent buildings and for any damage caused in consequence of these Works. They must reinstate all damages at his own expense and indemnify the Employer against any loss. The Contractor must take such steps and exercise such care and diligence as to minimize nuisance from dust, noise or any other cause to the occupiers of the existing and adjacent property.	
B	**HOARDING** The Contractor shall enclose the site areas under which work is carried out, with 1.80 meter high barbed wire fence comprising treated blue gum poles at centres not exceeding 3.0meters and 6No barbed wire strands at equal spacing The contractors attention is drawn to the fact that some areas of the site are already built up and shall be in use during the currency of this project. As such the contractor must allow for keeping his/her employees from interfering with such other users and preventing and minimizing any nuisance arising from dust, noise or by way of trespass. Allow for Provisional length of 100 meters @_____(tenderer to insert rate and extend)	
B	**WATCHING AND LIGHTING** The Contractor shall provide at their risk and cost all watching and lighting as necessary to safeguard the Works, plant and materials against damage and theft.	19,500.00
C	**SIGNBOARD** The Signboard and lettering on same for the display of the General and Sub-Contractors' names shall be of an approved size with the Employer's name painted thereon. The engineer's Quantity Surveyor's and other Consultants' names shall be printed in 50 mm letters all to the Architect's approved design. No other signboard or advertising will be permitted without prior permission from the Architect.	6,500.00
	Carried To Collection **KSH**	**26,000.00**

A	**PRIME COST RATES** Where description of items include a P.C. rate per unit this rate is to cover the net supply cost of the unit only. The Contractor's price must include for the cost of the unit at the rate stated, plus waste, taking delivery, storage, fixing in position, profit and overheads. The actual net cost per unit will be adjusted within the Final Account against the P.C. rate stated.	
	PROTECTION AND CLEANING	
B	**PROTECTION** The Contractor shall cover up and protect from damage, including damage from inclement weather, all finished work and unfixed materials, including that of Sub-Contractors, etc., to the satisfaction of the Architect until the completion of the Contract.	
C	**CLEANING** The Contractor shall, upon completion of the Works, at their own expense, remove and clear away all surplus excavated materials, plant, rubbish and unused materials and shall leave the whole of the Site and Works in a clean and tidy state to the satisfaction of the Architect, including clearing away and making good all traces of temporary access roads, offices, sheds, camps, etc. Particular care shall be taken to leave clean all floors and windows and to remove all paint and cement stains. They shall also, at the discretion of the Architect, remove all rubbish and dirt as it accumulates. The Contractor is to find their own dump and shall pay all charges in connection therewith.	15,600.00
	Carried To Collection **KSH**	**15,600.00**

	Collection		
	Brought forward from Page	1/3	-
	Brought forward from Page	1/4	15,600.00
	Brought forward from Page	1/5	26,000.00
	Brought forward from Page	1/6	127,400.00
	Brought forward from Page	1/7	42,900.00
	Brought forward from Page	1/8	87,100.00
	Brought forward from Page	1/9	26,000.00
	Brought forward from Page	1/10	15,600.00
	TOTAL FOR SECTION 1: PRELIMINARIES AND GENERAL	**KSH**	**340,600.00**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 2/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
	GROUND FLOOR				
1	**ELEMENT No.1 : SUBSTRUCTURE:**				
1.1	Clear site including grubbing up all bushes and remove vegetable top soil and remove all debris from site	666.4	m^2	65.00	43,316.00
1.2	Excavate for strip foundation trenches 800mm wide commencing at oversite level and not exceeding 1200mm and carting away to spoil as directed by the site supervisor	307.2	m^3	1,300.00	399,360.00
1.3	Excavate for column pad footings size 1,000x1,000mm commencing at oversite level and not exceeding 1200mm and carting away to spoil as directed by the site supervisor	72	m^3	1,300.00	93,600.00
1.4	Return, fill and ram selected excavated materials around foundations in 150mm deep layers	99.96	m^3	1,300.00	129,948.00
1.5	Supply, fill and ram good quality material as fill in layers of 100mm thick below the floor slab and as backfill to foundations	66.64	m^3	650.00	43,316.00
	Supply vibrated plain concrete class 15/20 with crushed aggregates as described:				
1.6	In blinding 50mm thick.	16	m^3	8,450.00	135,200.00
	Supply vibrated plain concrete class 20/20 with crushed aggregate as described:				
1.7	In strip foundation 200 mm thick	25.6	m^3	16,250.00	416,000.00
1.8	In column footing and columns	72	m^3	16,250.00	1,170,000.00
1.9	In floor slab 100mm thick and 100mm thick to 600mm wide paving around the building	66.64	m^3	16,250.00	1,082,900.00
	High Yield steel reinforcement bars, characteristic strength not less than 425N/mm2, to BS 4466:1969, cut, bent, and fixed including all necessary binding wire and spacer bars:				
1.10	Y10mm diameter bars in strip footing	421.6	Kg	260.00	109,616.00
1.11	Y8 mm diameter bars in strip footing as links	245.3	Kg	260.00	63,778.00
1.12	Y10mm diameter bars in column footing	361	Kg	260.00	93,964.00
1.13	Y12mm diameter bars in column starter bars	121.55	Kg	260.00	31,603.00
1.14	Y16mm diameter bars in column starter bars	433.20	Kg	260.00	112,632.00
1.15	Y8mm diameter bars as links in column	100.50	Kg	260.00	26,130.00
1.16	**Supply Cement sand blocks prepared in the 1:3 ratio** Construct stone wall in foundation, 40cm thickness bedded and jointed with cement sand mortar of 1:4 proportion (1 cement: 4 clean coarse sand) up to a height of 120cm. Face of wall should be in plumb. Corner stone should be good stones dressed to correct angles and laid as headers and stretchers. Bond stones shall be provided 100cm c/c vertically and horizontally. Wall should be laid in courses of 40cm height. All the gaps between stones shall be filled with cement mortar and wall should be kept moist for a period of at least 10 days and should be protected from sun.	153	m3	6,500.00	994,500.00
	Sub-total carried forward to next page				**4,945,863.00**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 3/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
	Hardcore				
1.17	300mm thick bed of quarry stones or equivalent material, well compacted and blinded with fine aggregate to receive concrete	199.6	m^3	455.00	90,818.00
	Supply and fix 25mm thick sawn formwork in softwood as described.				
1.18	150mm high to edges of concrete floor slab.	99.6	m	260.00	25,896.00
	Damp proof course				
1.19	200mm wide hessian based bituminous damp proof course to BS 743 type SA under walls lapped 150mm at joints laid on cement levelling screed	320	m	260.00	83,200.00
1.20	1000g polythene sheeting on top of murram blinding including 100mm laps	666.4	m^2	130.00	86,632.00
1.21	A98 mesh to ground floor slab including 100mm laps	666.4	m^2	910.00	606,424.00
	Total carried forward to summary page				**892,970.00**
2	**ELEMENT No.2 : WALLS**				
	Supply Cement sand blocks prepared in 1:3 cement sand ratio				
2.1	200mm thick cement/sand blocks external wall reinforced in hoop iron at every alternate course with v 20 swg x 25mm wide and embeded to RC columns	1120	m^2	1,300.00	1,456,000.00
	Total carried forward to summary page				**1,456,000.00**
3	**ELEMENT No.3: REINFORCED CONCRETE** **Cast in-situ vibrated reinforced concrete mix 1:2:4 Crushed aggregate as described:**				
3.1	Beam 500mm x 200mm.	32	m^3	16,250.00	520,000.00
3.2	Columns at ground floor 200 x 400mm	16.8	m^3	16,250.00	273,000.00
	Staircase				
3.3	1st and 2nd flight	1.78	m^3	16,250.00	28,925.00 0.00
3.4	150mm Thick landing	1.4	m^3	16,250.00	22,750.00
	Slab				0.00
3.5	175mm Thick suspended floor slab	116	m^3	16,250.00	1,885,000.00
	Supply and fix sawn formwork in softwood as described.				
3.6	Sides and soffits of beams	98.67	sm	390.00	38,481.30
	Sub-total carried forward to next page				**2,768,156.30**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 4/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
3.7	Sides of columns 200-300mm	387.85	sm	390.00	151,261.50
3.8	Soffits of suspended floor slab	372.36	sm	390.00	145,220.40
3.9	Soffits of landing	5.44	sm	390.00	2,121.60
3.10	Sloping soffits of staircase	8.928	sm	390.00	3,481.92
3.11	Edges of staircase strings 225-300mm high including cutting to profile of treads and risers	11.16	Lm	292.50	3,264.30
3.12	Edges of risers 150-225mm high	32	Lm	260.00	8,320.00
3.13	Edges of suspended floor slab 150-225mm high	87.8	Lm	227.50	19,974.50
3.14	Edges of landing 75-150mm high	8.9	Lm	195.00	1,735.50
3.15	Allow for scaffolding & props		Item	130,000.00	130,000.00
	High Yield steel reinforcement bars, characteristic strength not less than 425N/mm2, to BS 4466:1969, and Mild Yeild steel of characteristic strengh 250N/mm2 cut, bent, and fixed including all necessary binding wire and spacer bars:				
	Beam 500 x 200mm				
3.16	Y16mm diameter bars in beam	421.9	Kg	260.00	109,694.00
3.17	Y12mm diameter bars in beam	528.89	Kg	260.00	137,511.40
3.18	Y8mm diameter bars as stirrups to beam	409.22	Kg	260.00	106,397.20
	Columns 300x 200mm				
3.19	Y16 mm diameter bars in columns	673.6	Kg	260.00	175,136.00
3.2	Y12mm diameter bars in columns	182.4	Kg	260.00	47,424.00
3.21	Y8mm diameter bars as stirrups to columns	205.4	Kg	260.00	53,404.00
	Staircase				
3.22	Y12mm diameter bars in staircase	201	Kg	260.00	52,260.00
					0.00
3.23	Y10mm diameter bars in staircase	83.47	Kg	260.00	21,702.20
	175mm thick Slab				
3.24	Y10mm diameter bars in slab	1074.29	Kg	260.00	279,315.40
3.25	Y12mm diameter bars in slab	2,384.83	Kg	260.00	620,055.80
	Total carried forward to summary page				**2,068,279.72**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 5/40	
ITEM	DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
4	**ELEMENT No.4: DOORS AND WINDOWS**				
	DOORS				
4.1	Supply 1000X2100mm imported high hardwood framed door with 600mm high funlight with glazing, 1 1/4" thick flush paneled door sashes with a 150x75mm softwood timber frame, 3 pairs of heavy quality brass oxidized hinges and 3lever mortice lock. The door to be painted in 3coats of clear furnish	18	Nr	32,500.00	585,000.00
					0.00
4.2	Supply 800X2100mm high hardwood framed door, 1 1/4" thick flush paneled door sashes with a 150x75mm softwood timber frame, 3 pairs of heavy quality brass oxidized hinges, two number 300mm and 150mm barrel bolts and 3lever mortice lock. The door to be painted in 3coats of clear furnish for WC	7	Nr	13,000.00	91,000.00
	WINDOWS				
4.3	Supply pre-factory made aluminium casement windows size 1000 x 1200 mm high, widow type W1, sliding type with handle. Rate to include glazing in 4mm thick glass and fixing of the window framing.	39	Nr	22,100.00	861,900.00
4.4	ditto but 600 x 600 mm high, window type W2, windows to WC/ stairwell	9	Nr	13,000.00	117,000.00
	Total carried forward to summary page				**1,654,900.00**
5	**ELEMENT No.5: FINISHINGS**				
	Plinth area finishes				
5.1	12mm thick cement and sand (1:3) wood float render to plinth area	128	sm	520.00	66,560.00
5.2	Prepare and apply 3 coat of black bituminous paint to render area	120	sm	390.00	46,800.00
	Sub-total carried forward to next page				**113,360.00**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 6/40	
ITEM	DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
	Floor & Staircase Finishings				
5.3	25mm thick cement screed mix 1:3 finished: smooth steel trowel finish to the floor	388.74	sm	520.00	202,144.80
	Tiles: 300 x 300 x 6mm thick coloured non-slip ceramic tiles jointed and pointed with matching cement and sand (1:3) mortar as described				
5.4	On floor & staircase	666.4	m^2	1,950.00	1,299,480.00
5.5	6 x 150mm high tile skirting	33.12	m^2	1,300.00	43,056.00
	Wall Finishings				
5.6	Apply 20mm thick plastering in two coats of cement sand mortar on walls , both inside and outside. Walls should be cured at least for one week after 24 hours of plastering	2240	m^2	390.00	873,600.00
	Upper Slab Finishings				
5.7	13mm thick 1:4 lime/gypsum plaster to soffit of slab to steel trowel finish	598.4	m^2	390.00	233,376.00
	Tiles laid on cement and sand (1:4) backing: fixing with approved tile adhesive: jointed and pointed in proprietry grout in approved patterns				
5.80	6mm thick polished ceramic wall tiles including matching border tiles and edge strips to WC to height of 1.5m	68.7	m^2	2,080.00	142,896.00
	Painting				
5.90	Supply and apply two coats of white wash on all plastered surfaces	2240	m^2	260.00	582,400.00
5.10	Supply and apply two coats of emulsion paint on all whitewashed area	2240	m^2	260.00	582,400.00
	Vents				
5.11	Supply and fix precast concrete vents of 1200x 300mm high to all external openings. Rate to include fixing of wire gauze/ mosquito netting	20	Nr	6,500.00	130,000.00
	Total carried forward to summary page				**4,089,352.80**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 7/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
6	**ELEMENT No.6: ELECTRICAL INSTALLATION**				
	Supply the following electrical wiring, english type to approval including fixing, connecting, cutting holes, chasings, conduiting and making good all finishes.				
6.1	Allow sum for wiring,conduiting, chasing, making good to all finishes, connection to Mains and testing to the whole building to approved standards including earthing with standard electrode.	1	Item	390,000.00	390,000.00
6.2	Control panel box complete with main switch and separation for the lighting and socket power systems, cooker control unit and water pump	1	Nr	19,500.00	19,500.00
6.3	Meter box including the provision of main switch and cut-outs at the metre box	1	Nr	4,550.00	4,550.00
6.4	One way One Gang Switch	23	Nr	390.00	8,970.00
6.5	Two gang switch	5	Nr	390.00	1,950.00
6.6	Ceiling lighting points complete with 11 watt engergy sever bulb	23	Nr	1,950.00	44,850.00
6.7	Security lights	7	Nr	1,950.00	13,650.00
6.8	1200mm long flouresent light fittting and lamps	7	Nr	3,900.00	27,300.00
6.9	Wall brackets lighting points complete with lamp	3	Nr	1,950.00	5,850.00
6.10	13Amp Socket outlets	30	Nr	390.00	11,700.00
6.11	Cooker control unit	1	Nr	1,300.00	1,300.00
6.12	Overhead fans "Oriental" or equal approved including the control and wiring	12	Nr	11,700.00	140,400.00
	Total carried forward to summary page				**670,020.00**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 8/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
7	**ELEMENT No. 7: PLUMBING AND SANITARY INSTALLATION** Supply assemble and fix the following sanitary fittings including all joints to services, overflow soil and waste pipe, jointing material, cutting or forming mortices and holes and making good as necessary (Reference to Armitarge Shanks are given as a guide to quality and type only an equal and approved British alternatives may be used.				
7.1	Provide the Provisional Sum for plumbing of all sanitary fittings in the toilet and gulley traps from WC,up to the respective inspection chambers and septic tank. Rate to include all the waste pipes and plumbing accessories	1	Item	45,500.00	45,500.00
7.2	Supply and fix 600 x 450 x 5mm thick polished plate glass mirror with holes for domex screws and fixing to the wall above the wash hand basin	6	Nr	3,900.00	23,400.00
7.3	Supply and fix white vitreous british or equivalent pedestal type water closet , squatting type, with a 10 liters low level flushing cisten complete with all fittings	6	Nr	19,500.00	117,000.00
7.4	Supply and fix white vitreous british or equivalent sink size 300x200mm to the WC including all piping and connections	6	Nr	9,750.00	58,500.00
7.5	Providing and fixing towel rail 600mm long complete with brackets fixed to wooden cleats with brass screws with concealed fittings arangement of approved quality colour	6	Nr	2,600.00	15,600.00
7.6	Recessed toilet roll holder	6	Nr	1,300.00	7,800.00
7.7	Supply and fix 100mm diameter heavy gauge PVC pipes to the toilets as vent pipes 4500mm long with the fly trap in place	6	Nr	6,500.00	39,000.00
7.8	Allow for testing the whole of the sanitary installation during the progress of the works and again on completion and leave in perfect working condition	1	Item	13,000.00	13,000.00
	Total carried forward to summary page				**319,800.00**

Ground Floor Total					18,978,701.82
BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 9/40	
ITEM	DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
	1ST FLOOR SLAB				
8	**ELEMENT No.8 : WALLS**				
	Supply Cement sand blocks prepared in 1:3 cement sand ratio				
8.1	200mm thick cement/sand blocks external wall reinforced in hoop iron at every alternate course with v 20 swg x 25mm wide and embeded to RC columns	1120	m^2	2,340.00	2,620,800.00
	Total carried forward to summary page				**2,620,800.00**
9	**ELEMENT No.9: REINFORCED CONCRETE Cast in-situ vibrated reinforced concrete mix 1:2:4 Crushed aggregate as described:**				
9.1	Beam 400mm x 200mm.	32	m^3	16,250.00	520,000.00
9.2	Columns at first floor 400 x 200mm	16.8	m^3	16,250.00	273,000.00
	Staircase				
9.3	1st and 2nd flight	1.78	m^3	16,250.00	28,925.00
9.4	150mm Thick landing	1.4	m^3	16,250.00	22,750.00
	175mm thick Slab				
9.5	175mm Thick suspended floor slab	116	m^3	16,250.00	1,885,000.00
	High Yield steel reinforcement bars, characteristic strength not less than 425N/mm2, to BS 4466:1969, and Mild Yeild steel of characteristic strengh 250N/mm2 cut, bent, and fixed including all necessary binding wire and spacer bars:				
	Beam 500x 200mm				
9.6	Y16mm diameter bars in beam	421.9	Kg	260.00	109,694.00
9.7	Y12mm diameter bars in beam	528.89	Kg	260.00	137,511.40
9.8	Y8mm diameter bars as stirrups to beam	409.22	Kg	260.00	106,397.20
	Columns				
9.9	Y16 mm diameter bars in columns	673.6	Kg	260.00	175,136.00
9.10	Y12mm diameter bars in columns	182.4	Kg	260.00	47,424.00
9.11	Y8mm diameter bars as stirrups to columns	205.4	Kg	260.00	53,404.00
	Sub-total carried forward to next page				**3,359,241.60**

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
	175mm thick Slab				
9.12	Y10mm diameter bars in slab	1074.29	Kg	260.00	279,315.40
9.13	Y12mm diameter bars in slab	2,384.83	Kg	260.00	620,055.80
	Staircase				
9.14	Y12mm diameter bars in staircase	201	Kg	260.00	52,260.00
					0.00
9.15	Y10mm diameter bars in staircase	83.47	Kg	260.00	21,702.20
9.16	Supply of hand rail & Balustrade Modular system of mild steel with metal primer and two coats of approved gloss paint. The system comprises handrail of 50mm & 3mm thick and 3 horizontal steel pipe of 25mm & 1.5mm thick diameter of equal spacing with balustrades of stainless pipe of 38mm & 3mm thick @ 1200mm C/C bolted/ welded to good finish and fixed/ grouted in concrete.	LS	1	195,000.00	195,000.00
	Total carried forward to summary page				**1,168,333.40**
10	**ELEMENT No.10: DOORS AND WINDOWS**				
	DOORS				
10.11	Supply 1000X2100mm high hardwood framed door with 600mm high funlight with glazing, 1 1/4" thick flush paneled door sashes with a 150x75mm softwood timber frame, 3 pairs of heavy quality brass oxidized hinges and 3lever mortice lock. The door to be painted in 3coats of clear furnish	17	Nr	33,800.00	574,600.00
10.2	Supply 800X2100mm high hardwood framed door, 1 1/4" thick flush paneled door sashes with a 150x75mm softwood timber frame, 3 pairs of heavy quality brass oxidized hinges, two number 300mm and 150mm barrel bolts and 3lever mortice lock. The door to be painted in 3coats of clear furnish	4	Nr	13,000.00	52,000.00
	WINDOWS				
10.3	Supply pre-factory made aluminium casement windows size 1000 x 1200 mm high, widow type W1, sliding type with handle. Rate to include glazing in 4mm thick glass and fixing of the window framing.	47	Nr	20,800.00	977,600.00
10.4	ditto but 600 x 600 mm high, window type W2, windows to WC/ stairwell	7	Nr	9,750.00	68,250.00
	Total carried forward to summary page				**1,672,450.00**

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
11	**ELEMENT No.11: FINISHINGS**				
	Plinth area finishes				
	Floor & staircase Finishings				
11.1	25mm thick cement screed mix 1:3 finished: smooth steel trowel finish to the floor	388.74	sm	520.00	202,144.80
	Tiles: 300 x 300 x 6mm thick coloured non-slip ceramic tiles jointed and pointed with matching cement and sand (1:3) mortar as described				
11.2	On floor & staircase	388.74	m^2	1,950.00	758,043.00
11.3	6 x 150mm high tile skirting	33.12	m^2	1,300.00	43,056.00
	Wall Finishings				
11.4	13mm thick 1:4 lime/gypsum plaster to internal walls to steel trowel finish	1102.5	m^2	260.00	286,650.00
11.5	13mm thick 1:4 lime/gypsum plaster to external surfaces of the beam/	5	m^2	260.00	1,300.00
11.6	Tylolean finish to external walls in approved color additive	1102.5	m^2	260.00	286,650.00
	Upper Slab Finishings				
11.7	13mm thick 1:4 lime/gypsum plaster to soffit of slab to steel trowel finish	596.68	m^2	260.00	155,136.80
	Tiles laid on cement and sand (1:4) backing: fixing with approved tile adhesive: jointed and pointed in proprietry grout in approved patterns				
11.8	6mm thick polished ceramic wall tiles including matching border tiles and edge strips to wc to height of 1.5m	45	m^2	1,950.00	87,750.00
	Painting				
11.9	Prepare and apply one undercoat and two coats of gloss paint on beam external	4.095	m^2	260.00	1,064.70
11.10	Prepare surface and paint one undercoat and two coats of emulsion paint on internal walls	1102.5	m^2	260.00	286,650.00
	Vents				
	Total carried forward to summary page				**2,108,445.30**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 12/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
12	**ELEMENT No.12: ELECTRICAL INSTALLATION** **Supply the following electrical wiring, english type to approval including fixing, connecting, cutting holes, chasings, conduiting and making good all finishes.**				
12.1	Allow sum for wiring,conduiting, chasing, making good to all finishes, connection and testing to the whole building to approved standards.	1	Item	78,000.00	78,000.00
12.2	One way One Gang Switch	23	Nr	390.00	8,970.00
12.3	Two gang switch	5	Nr	390.00	1,950.00
12.4	Ceiling lighting points complete with 11 watt engergy sever bulb	23	Nr	1,950.00	44,850.00
12.5	Garden lamps coloured lights	20	Nr	1,950.00	39,000.00
12.6	1200mm long flouresent light fittting and lamps	8	Nr	3,900.00	31,200.00
12.7	Wall brackets lighting points complete with lamp	3	Nr	1,950.00	5,850.00
12.8	13Amp Socket outlets	30	Nr	390.00	11,700.00
12.9	Overhead fans "Oriental" or equal approved including the control and wiring	10	Nr	11,700.00	117,000.00
	Total carried forward to summary page				**338,520.00**
13	**ELEMENT No. 13: PLUMBING AND SANITARY INSTALLATION** Supply assemble and fix the following sanitary fittings including all joints to services, overflow soil and waste pipe, jointing material, cutting or forming mortices and holes and making good as necessary (Reference to Armitarge Shanks are given as a guide to quality and type only an equal and approved British alternatives may be used.				
13.1	Provide the Provisional Sum for plumbing of all sanitary fittings in the toilet and gulley traps from WC,up to connection to WC of lower floors tank. Rate to include all the waste pipes and plumbing accessories	1	Item	45,500.00	45,500.00
13.2	Supply and fix 600 x 450 x 5mm thick polished plate glass mirror with holes for domex screws and fixing to the wall above the wash hand basin	2	Nr	3,900.00	7,800.00
13.3	Supply and fix white vitreous british or equivalent pedestal type water closet , squatting type, with a 10 liters low level flushing cisten complete with all fittings	4	Nr	19,500.00	78,000.00
	Total carried forward to next page				**131,300.00**

BILL OF QUANTITIES - CONSTRUCTION OF Immigration HQ OFFICES in Mombasa		BILL NO. 1		PAGE NO. 13/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
13.4	Supply and fix white vitreous british or equivalent sink size 300x200mm to the WC including all piping and connections	4	Nr	9,750.00	39,000.00
13.5	Providing and fixing towel rail 600mm long complete with brackets fixed to wooden cleats with brass screws with concealed fittings arangement of approved quality colour	4	Nr	2,600.00	10,400.00
13.6	Recessed toilet roll holder	4	Nr	1,300.00	5,200.00
13.7	Supply and fix 100mm diameter heavy gauge PVC pipes to the toilets	4	Nr	9,750.00	39,000.00
13.8	Allow for testing the whole of the sanitary installation during the progress of the works and again on completion and leave in perfect working condition	1	Item	13,000.00	13,000.00
	Total carried forward to summary page				**106,600.00**
	TERRACE				
14	**ELEMENT No.14 : WALLS**				
	Supply Cement sand vented blocks prepared in 1:3 cement sand ratio				
14.1	150-200mm thick concrete vent block to the Engineer approval with a concrete coping and embeded to the RC columns	130.2	m^2	1,560.00	203,112.00
	Total carried forward to summary page				**203,112.00**

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
15	**ELEMENT No.15 : tile** **Tiles laid on cement and sand (1:4) backing: fixing with approved tile adhesive: jointed and pointed in proprietry grout in approved patterns**				
15.1	6mm thick polished concrete floor including matching border tiles and edge strips	666.4	sm	1,300.00	866320.00
	Total carried forward to summary page				**866,320.00**
16	**STAIRCASE SHELTER** **ELEMENT No.16 : 300mm PARAPET WALLS** **Supply Cement sand blocks prepared in 1:3 cement sand ratio**				
16.1	200mm thick cement/sand blocks external wall reinforced in hoop iron at every alternate course with v 20 swg x 25mm wide with concrete coping top	32.16	m^2	1,560.00	50169.60
	Total carried forward to summary page				**50169.60**
	ELEMENT No.17: REINFORCED CONCRETE **Cast in-situ vibrated reinforced concrete mix 1:2:4 Crushed aggregate as described:**				
17.1	Beam 400mm x 200mm.	25.2	m^3	16,250.00	409500.00
	150mm thick Slab				
17.2	150mm Thick suspended floor slab	99.96	m^3	16,250.00	1624350.00
	Columns 300mm x 200mm	2.4	m^3	16,250.00	39000.00
	High Yield steel reinforcement bars, characteristic strength not less than 425N/mm2, to BS 4466:1969, and Mild Yeild steel of characteristic strengh 250N/mm2 cut, bent, and fixed including all necessary binding wire and spacer bars:				
	Beam 300x 200mm				
17.3	Y12mm diameter bars in beam	80.5	Kg	260.00	20930
17.4	Y8mm diameter bars as stirrups to beam	55.6	Kg	260.00	14456
	150mm thick Slab				
17.5	Y12mm diameter bars in slab	223.60	Kg	260.00	58136
	Total carried forward to next page				**2,166,372.00**

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
	Columns at stairwell				
17.6	Y16 mm diameter bars in columns	110.7	Kg	260.00	28782
17.7	Y12mm diameter bars in columns	48.2	Kg	260.00	12532
17.8	Y8mm diameter bars as stirrups to columns	46.8	Kg	260.00	12168
	Total carried forward to summary page				**53,482.00**
18	**ELEMENT No.18 Plumbing works**				
18.1	Supply and install a 2000 liter plastic tank; maximum diameter 1350mm, height 1580mm, or equal and approved make, on the roof including 25mm diameter uPVC PPR pipes and all piping accessories	2	Nr	65,000.00	130000.00
18.2	Submersible pump, 0.55KW "pedrollo Top Multi 2" or equal and approved make, with a minimum head of 25m at 30litres/ minute, complete with drop down cables and accessories for connection to mains.	1	Nr	19,500.00	19500.00
18.3	Allow for PVC 4" down pipes from the canopy including grating and respective joints and anchorage	1	Item	39,000.00	39000.00
18.4	Excavate and construct 15m3 underground water tank complete with RCC work of slab, walls, and floor	1	Item	390,000.00	390000.00
	Total carried forward to summary page				**578500.00**
	TOTAL COST 1ST FLOOR				**15,423,645.90**
	Grand Total(ground floor +first floor)				**34,402,347.72**

BILL OF QUANTITIES - CONSTRUCTION OF A SEPTIC TANK Immigration HQ					
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
1	**ELEMENT No.1 : SEPTIC TANK AND DRAINAGE WORKS**				
1.1	Excavate for septic tank, manholes, inspection chambers and pit and soak away pit as per the drawings	30	m^3	3,900.00	117,000.00
1.2	Spread excavated materials as directed by the site supervisor	30	m^3	1,300.00	39,000.00
	Supply vibrated plain concrete class 15/20 with crushed aggregates as described:				
1.3	In blinding 50mm thick.	0.7	m^3	8,450.00	5,915.00
	Supply vibrated plain concrete class 20/20 with crushed aggregate as described:				
1.4	**150mm thick in strip foundation and bottom slab to septic tank and inspection chambers**	3.2	m^3	17,160.00	54,912.00
	Total carried forward to summary page				216,827.00
2	**Supply Cement sand blocks prepared in the 1:3 ratio**				
2.1	200mm thick cement/sand blocks external wall reinforced in hoop iron at every alternate course	70	m^2	1,300.00	91,000.00
	Total carried forward to summary page				91,000.00
3	**Hardcore to soak away pit**				
3.1	**200mm thick quarry stones**	3	m^3	1,300.00	3,900.00
	Total carried forward to summary page				3,900.00
4.00	Unwrot formwork to soffits of septic tank, soak away pit				
4.1	25mm thick including all props	11	m^2	4,550.00	47,775.00
4.2	150mm high to edges of the slabs	21.5	m	1,300.00	27,950.00
	Total carried forward to summary page				75,725.00
5	Cast in-situ vibrated reinforced concrete mix 1:2:4 Crushed aggregate as described:				
5.1	Slabs to septic tank and soak away pit	5	m^3	19,500.00	97,500.00
	Total carried forward to summary page				**97,500.00**

ITEM	BILL OF QUANTITIES - CONSTRUCTION OF A SEPTIC TANK Immigration HQ DESCRIPTION	QTY	UNIT	RATE	TOTAL (KSH)
6.00	**High yield steel reinforcement bars, characteristic strength not less than 425N/mm2, to BS 4466:1969, and Mild Yeild steel of characteristic strengh 250N/mm2 cut, bent, and fixed including all necessary binding wire and spacer bars:**				
6.1	**Y12mm diameter bars to septic tank slab**	65	Kg	260.00	16,900.00
6.2	Y10mm diameter bars to septic tank and soak-away pits	37.5	Kg	260.00	9,750.00
	Total carried forward to summary page				26,650.00
7	**Finishings**				
	Cement and sand (1:3)				
7.1	**25mm thick cement screed mix 1:3 finished to wooden float finish to the floor of the inspection chambers and gulley traps**	3	m^2	650.00	**1,950.00**
7.2	Ditto but to septic tank with water proofing cement to applied to manufacturer's instructions	6.5	m^2	650.00	4,225.00
7.3	13mm thick 1:4 lime/gypsum plaster to internal walls of the inspection chambers and gulley traps and finishing of the top surfaces of soak away pit, placenta pit and all the Ics and GTs to smooth trowel finish	21	m^2	650.00	13,650.00
7.4	Ditto but to walls of the septic tank in water proof cement	23	m^2	1,950.00	44,850.00
	Total carried forward to summary page				**64,675.00**
8	**Inspection Chamber covers**				
8.1	600x450mm standard cast iron covers to Inspection chambers	7	Nr	9,100.00	63,700.00
	Total carried forward to summary page				**63700**
	Total cost of septic tank				**639,977.00**

No	DESCRIPTION	QUANTITY	UNIT	Unit Price KSH	Total Amount KSH
	Construction of 2 offices and one waiting hall for Immigration HQ				
	Element No: 1.SUBSTRUCTURE				
1.0	**Substructure**				
1.1	Clearance site including grubbing up all bushes and remove vegetable top soil and remove all debris from the site	84.62	m²	65.00	5500.30
1.2	Excavate for strip foundation trenches 600mm wide and 500mm deep commencing at the oversite level and cart away to spoil as directed by the engineer	13.20	m³	1300.00	17160
1.3	Excavate for column pad footings size 400 x 400mm commencing at oversite level and not exceeding 600mm and carting away to spoil as directed by the site	1.152	m3	1,300.00	1497.6
1.3	Return ,fill and ramp selected excavated materials around foundation in 150mm deep layers	12.00	m³	1300.00	15,600.00
	Supply vibrated plain concrete class 15/20 with crushed aggregates as described;				
1.4	In blinding 50mm thick at bottom of the foundation	1.32	m³	14300.00	18,876.00
	Supply vibrated plain concrete class 20/20 with crushed aggregates as described;				
1.5	In column footing and columns	1.15	m³	16250.00	18,720.00
	strength not less than 425mmN/mm2 ,to BS 4466: cut ,bent, and fixed including all necessary binding wire				
1.6	Y10mm diameter bars in strip footing	100.00	KG	143.00	14,300.00
1.7	R6 Diameter bars in strip footing as links	75.00	KG	109.20	8,190.00
1.8	Y10mm diameter bars in column footing	150.00	KG	143.00	21,450.00
1.9	Y12mm diameter bars in starter bars	100.00	KG	143.00	14,300.00
1.10	R6 Diameter bars as links in column	121.00	KG	109.20	13,213.20
1.11	Y12mm diameter bars in foundation walls	200.00	KG	143.00	28,600.00
	Total carried to summary				**177,407.10**

No	DESCRIPTION	QUANTITY	UNIT	Unit Price KSH	Total Amount KSH
2	**ELEMENT NO.2 REINFORCED FLOOR**				
	Hardcore				
2.1	200mm hardcore thick bed of quarry stones or equivalent materials, well compacted and blinded with fine aggregate to receive aggregates	16.90	m^3	1950.00	32,955.00
	Supply vibrated plain concrete class 20/20 with crushed aggregates as described;				
2.2	Concrete floor 100mm thick	8.46	m^3	11700.00	99,005.40
	wood as described				
2.3	150mm high to edges of concrete floor slab	88.00	m	325.00	28,600.00
	Damp proof course				
2.4	Provide and receive 1000g polythene sheeting on top of murram blinding including 100mm laps	84.62	m^2	390.00	33,001.80
2.5	A98 Mesh to ground floor slab including 100mm laps	84.62	m^2	390.00	33,001.80
	Total carried to summary				**226,564.00**
3	**ELEMENT No: 3 WALLING**				
3.1	**Supply cement sand blocks prepared in 1:3 sand ratio**				
3.2	200mm thick cement/sand blocks for external and internal walls	154.00	m^2	1300.00	200,200.00
3.3	**Cast in-situ vibrated reinforced concrete mix (1:2:4) crushed aggregate as described**				
	High yield steel reinforcement bars, characteristic strength not less than 425mmN/mm2 ,to BS 4466: cut				
3.5	Y10diameter bars for ring beams	160.10	KG	143.00	22,894.30
3.6	R6 diameter bars as links or as strups to ring beams	55.00	KG	109.20	6,006.00
	Total carried to next page				**229,100.30**

No	DESCRIPTION	QUANTITY	UNIT	Unit Price KSH	Total Amount KSH
	described				
3.7	Sides of columns and foundation beams 200mm-300mm	119.50	m^2	812.50	97,093.75
	Cast in-situ vibrated reinforced concrete mix (1:2:4) crushed aggregate as described				
3.8	the walls	1.76	m^3	16250.00	28,600.00
	strength not less than 425mmN/mm2 ,to BS 4466: cut				
3.9	Y12 diameter bars for ring beams	300.00	KG	143.00	42,900.00
3.10	R6 diameter bars as links or as strups to ring beams	150.00	KG	109.20	16,380.00
	Supply and fix Sawn formwork in soft wood as described				
3.11	Sides of columns and ring beams with thick 200mm wide and 200mm high	250.00	m	325.00	81,250.00
	Total Carried to summary				**266,223.75**
4	**ELEMEN. N0 4 WALL FINISHINGS AND PAINTINGS**				
	Wall finishing				
4.1	13mm thick (1:4) lime /gypsum plaster to internal walls with to steel trowel	154	m^2	390.00	60,060.00
4.2	13mm thick (1:4) lime /gypsum plaster to external walls with to steel trowel	154	m^2	390.00	60,060.00
	Total carried out				**120,120.00**

No	DESCRIPTION	QUANTITY	UNIT	Unit Price KSH	Total Amount KSH
5	**ELEMENT N0: 5 ROOFING**				
	Supply and fix the following in treated softwood Sawn cypress on roof trusses. this to include fabrication				
5.1	Supply and constuct roof including truss members, galvanised iron sheets gauge 28 complete with nails, straps and secured with iron bars embedded into tie beam. The truss members, common rafters, gusset plates, struts, purlins and ceiling joists are in hard wood and of the following section:	85.62	m2	2340.00	200,350.80
	Total carried to summary				**200,350.80**
6	**ELEMENT N0 6 CEILINGS :**				
6.1	provide ceiling board cypress 4mm thick brandering at 50x50mm thick cypress brandering at 600mm to center centers both sides	85.62	m^2	520.00	44,522.40
	Total carried forward to summary page				**44,522.40**
7	**ELEMENT N0 : 7.FLOOR FINISHINGS**				
7.1	Cement and sand (1:4) screeds and paving on concrete 40mm thick steel troweled screed with red oxide pigment incase is proposed	85.62	m^2	520.00	44,522.40
	Total carried forward to summary page		`		**44,522.40**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price KSH**	**Total Amount KSH**
8	**ELEMENT NO 8 PAINTING AND DECORATIONS**				
8.1	Prepare surface and paint one undercoat and two coats of emulsion paints on internal walls	154	m^2	260.00	40,040.00
8.2	Prepare and apply two coats of white cream emulsion paint, soffits of chipboard ceilings	85.62	m^2	390.00	33,391.80
8.3	prepare surface and paint one undercoat and two coats of emulsion paints on external walls	154	m^2	260.00	40,040.00
8.5	Apply two coats of paint on fascia board	74.8	m^2	325.00	24,310.00
	Total carried forward to summary page				**137,781.80**
9	**ELEMENT NO: 9 DOORS AND WINDOWS**				

	50mmx100mm wide timber boarding with tougned and grooved joints 150mmx50mm stiles bottom and				
9.1	Supply 900mmx2100mm high hard wood framed 1 1/4 " thick flush paneled door sashes with a 100x50mm soft	2	pcs	13000.00	26,000.00
9.2	Supply and install 700mm x 2100mm high steel door in 38mm x 25mm x 3mm thick RHS framing, and 3mm thick sheet plate, 3 pairs of heavy quantity brass oxidized hinges, two number 150mm barrel bolts and a 264 " tri-circle" or equal approved padlock with a set 3 original keys. The door to be painted in 3 coats of gloss paint.	1	pcs	7800.00	7,800.00
	Supply and fix metal windows in metal frames, complete with shutters, fittings and wire mesh - Window size 1500x2000mm .	3	pcs	7,800.00	23,400.00
9.3	Supply and install 500mm wide and 500mm high steel grill with mosquito screen for latrines	4	pcs	3900.00	15,600.00
	Total carried forward to summary page				**72,800.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price KSH**	**Total Amount KSH**
10	**ELEMENT N0: 10. ELECTRICAL INSTALLATION**				
	including fixing, connecting, cutting holes,chasings,				
10.1	Allow sum for wiring, conduiting,chasing and good making to all finishes,connection and test to the whole building to be approved starndrads	1	Item	32500.0	32,500.00
10.2	control panel box complete with main switch and seperatio for the lighting and socket power system	1	Nr	7800.00	7,800.00
10.3	Meter box including the provison of main switch and cut outs at the meter box	1	Nr	6500.00	6,500.00
10.4	one way one gang switch	3	Nr	1300.00	3,900.00
10.5	Sockets	5	Nr	1040.00	5,200.00
10.6	Two gang switch	3	Nr	1040.00	3,120.00
10.7	flourscent fitting 4ft complete with lamp	5	Nr	1300.00	6,500.00
	Total carried forward to summary page				**65,520.00**
	GRAND TOTAL COST FOR Building				**KES 1,584,912.55**

BILL OF QUANTITIES - CONSTRUCTION OF Fence wall for Immigration HQ					
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
1	**ELEMENT No.1 : SUBSTRUCTURE:**				
1.1	Clear site including grubbing up all bushes and remove vegetable top soil and remove all debris from site	5600	m^2	39.00	218,400.00
1.2	Excavate for strip foundation trenches 600mm wide commencing at oversite level and not exceeding 600mm and carting away to spoil as directed by the site supervisor	144	m^3	1,300.00	187,200.00
1.3	Excavate for column pad footings size 1000 x 1000mm commencing at oversite level and not exceeding 600mm and carting away to spoil as directed by the site supervisor	24	m^3	1,950.00	46,800.00
1.4	Return, fill and ram selected excavated materials around foundations in 150mm deep layers	840	m^3	260.00	218,400.00
	Supply vibrated plain concrete class 15/20 with crushed aggregates as described:				
1.5	In blinding 50mm thick.	15	m^3	4,550.00	68,250.00
	Supply vibrated plain concrete class 20/20 with crushed aggregate as described:				
1.6	In strip foundation 200 mm thick	96	m^3	11,700.00	1,123,200.00
	In column footing (1000x 1000mm base)and column adjoining the main gate	24	m^3	11,700.00	280,800.00
	High Yield steel reinforcement bars, characteristic strength not less than 425N/mm2, to BS 4466:1969, cut, bent, and fixed including all necessary binding wire and spacer bars:				
1.7	Y10mm diameter bars in strip footing	500.8	Kg	260.00	130,208.00
1.8	Y8 mm diameter bars in strip footing as links @ 200mm spacing	450.12	Kg	260.00	117,031.20
	Total carried forward to next page				**2,390,289.20**

BILL OF QUANTITIES - CONSTRUCTION OFENCE WALL FOR IMMIGRATION HQ		BILL NO. 5		PAGE NO. 37/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
	In 600x 600mm column as gate anchor				
1.90	Y10mm diameter bars in column footing	14.78	Kg	260.00	3,843.84
1.10	Y12mm diameter bars in column starter bars	11.366	Kg	260.00	2,955.16
1.11	Y8mm diameter bars as links in column @ 200mm spacing	8.22	Kg	260.00	2,136.16
	In 400x 400mm along the boundary wall				
1.12	Y10mm diameter bars in column footing	170.02	Kg	260.00	44,204.16
1.13	Y12mm diameter bars in column starter bars	196.07	Kg	260.00	50,978.20
1.15	Y8mm diameter bars as links in column @ 200mm spacing	196.24	Kg	260.00	51,021.36
	Supply Masonry dressed Quarry stones				
1.16	400mm thick dressed masonry walling laid in regular course in hoop iron at every alternate course	207	m^2	1,300.00	269,100.00
	Total carried forward to summary page				**424,238.88**
2	**ELEMENT No.2 : WALLS**				
	Supply Cement sand blocks prepared in 1:3 cement sand ratio				
2.1	200mm thick cement/sand blocks external wall reinforced in hoop iron at every alternate course with v 20 swg x 25mm wide and embeded to RC columns	780	m^2	1,300.00	1,014,000.00
	Total carried forward to summary page				**1,014,000.00**

BILL OF QUANTITIES - CONSTRUCTION OF FENCE Wall FOR iMMIGRATION HQ		BILL NO. 5		PAGE NO. 38/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
3	**ELEMENT No.3: REINFORCED CONCRETE** **Cast in-situ vibrated reinforced concrete mix 1:2:4 Crushed aggregate as described:**				
3.1	Columns 600 x 600mm	3.6	m^3	13,000.00	46,800.00
3.2	Columns 400 x 400mm	30.496	m^3	13,000.00	396,448.00
	Supply and fix sawn formwork in softwood as described.				
3.3	Sides of columns 600-800mm	136.8	sm	130.00	17,784.00
	High Yield steel reinforcement bars, characteristic strength not less than 425N/mm2, to BS 4466:1969, and Mild Yeild steel of characteristic strengh 250N/mm2 cut, bent, and fixed including all necessary binding wire and spacer bars:				
	In 600x 600mm column at gate				
3.4	Y12mm diameter bars in columns	68.2	Kg	195.00	13,299.00
3.5	Y8mm diameter bars as stirrups to columns @ 200mm spacing	50.32	Kg	195.00	9,812.40
	In 400x 400mm along the boundary wall				
3.6	Y12mm diameter bars in columns	500.12	Kg	195.00	97,523.40 0.00
3.7	Y8mm diameter bars as stirrups to columns @ 200mm spacing	405.3	Kg	195.00	79,033.50
	Total carried forward to summary page				**660,700.30**
4	**ELEMENT No.4: FINISHINGS**				
	Wall Finishings				
4.1	13mm thick 1:4 lime/gypsum plaster to internal walls to steel trowel finish	780	m^2	130.00	101,400.00
4.2	13mm thick 1:4 lime/gypsum plaster to external surfaces	780	m^2	130.00	101,400.00
	Total carried forward to next page				**202,800.00**

BILL OF QUANTITIES - CONSTRUCTION OF FENCE wall FOR IMMIGRATION HQ		BILL NO. 5		PAGE NO. 39/40	
ITEM	**DESCRIPTION**	**QTY**	**UNIT**	**RATE (KSH)**	**TOTAL (KSH)**
	Painting				
4.5	Prepare surface and paint one undercoat and two coats of emulsion paint on internal walls	780	m^2	130.00	101,400.00
4.6	Prepare surface and paint one undercoat and two coats of emulsion paint on external walls	780	m^2	130.00	101,400.00
	Total carried forward to summary page				**202,800.00**
5	**ELEMENT No. 5: Supply and fix gate**				
5.1	Provide standard main gate of size 4mx2.4 wide including painting of the Gate supported by the RCC columns at sides to support the metal gate	2	Nr	52,000.00	104,000.00
	Total carried forward to summary page				**104,000.00**
	TOTAL COST FOR BOUNDRY WALL				4,998,828.38

No	DESCRIPTION	QUANTITY	UNIT	Unit Price KSH	Total Amount KSH ()
Construction of Guard rooms for Immigration HQ					
	Element No: 1.SUBSTRUCTURE				
1.0	**Substructure**				
1.1	Clearance site including grubbing up all bushes and remove vegetable top soil and remove all debris from the	40.00	m²	65.00	2600.00
1.2	Excavate for strip foundation trenches 600mm wide and 500mm deep commencing at the oversite level and cart away to spoil as directed by the engineer	13.20	m³	1300.00	17160
1.3	Excavate for column pad footings size 400 x 400mm commencing at oversite level and not exceeding 600mm and carting away to spoil as directed by the site supervisor	1.152	m3	1,300.00	1497.6
1.3	Return ,fill and ramp selected excavated materials around foundation in 150mm deep layers	6.00	m³	1300.00	7,800.00
	Supply vibrated plain concrete class 15/20 with crushed aggregates as described;				
1.4	In blinding 50mm thick at bottom of the foundation	2.20	m³	16250.00	35,750.00
	Supply vibrated plain concrete class 20/20 with crushed aggregates as described;				
1.5	In column footing and columns	1.15	m³	14300.00	16,473.60
	strength not less than 425mmN/mm2 ,to BS 4466: cut ,bent, and fixed including all necessary binding wire				
1.6	Y10mm diameter bars in strip footing	68.20	KG	143.00	9,752.60
1.7	R6 Diameter bars in strip footing as links	45.10	KG	109.20	4,924.92
1.8	Y10mm diameter bars in column footing	75.10	KG	143.00	10,739.30
1.9	Y12mm diameter bars in starter bars	100.00	KG	143.00	14,300.00
1.10	R6 Diameter bars as links in column	60.20	KG	109.20	6,573.84
1.11	Y12mm diameter bars in foundation walls	100.00	KG	143.00	14,300.00
	Total carried to summary				**141,871.86**

No	DESCRIPTION	QUANTITY	UNIT	Unit Price KSH	Total Amount KSH ()
2	**ELEMENT NO.2 REINFORCED FLOOR**				
	Hardcore				
2.1	200mm hardcore thick bed of quarry stones or equivalent materials, well compacted and blinded with fine aggregate to receive aggregates	8.80	m^3	1950.00	17,160.00
	Supply vibrated plain concrete class 20/20 with crushed aggregates as described;				
2.2	Concrete floor 100mm thick	4.00	m^3	14300.00	57,200.00
	wood as described				
2.3	150mm high to edges of concrete floor slab	88.00	m	325.00	28,600.00
	Damp proof course				
2.4	Provide and receive 1000g polythene sheeting on top of murram blinding including 100mm laps	40.00	m^2	390.00	15,600.00
2.5	A98 Mesh to ground floor slab including 100mm laps	40.00	m^2	390.00	15,600.00
	Total carried to summary				**134,160.00**
3	**ELEMENT No: 3 WALLING**				
3.1	**Supply cement sand blocks prepared in 1:3 sand ratio**				
3.2	200mm thick cement/sand blocks for external and internal walls	154.00	m^2	1300.00	200,200.00
3.3	**Cast in-situ vibrated reinforced concrete mix (1:2:4) crushed aggregate as described**				
	High yield steel reinforcement bars, characteristic strength not less than 425mmN/mm2 ,to BS 4466: cut				
3.4	Y10diameter bars for ring beams	85.30	KG	143.00	12,197.90
3.5	R6 diameter bars as links or as strups to ring beams	30.50	KG	109.20	3,330.60
	Total carried to next page				**215,728.50**

No	DESCRIPTION	QUANTITY	UNIT	Unit Price KSH	Total Amount KSH ()
	described				
3.6	Sides of columns and foundation beams 200mm-300mm	70.20	m^2	812.50	57,037.50
	Cast in-situ vibrated reinforced concrete mix (1:2:4) crushed aggregate as described				
3.7	the walls	0.80	m^3	20150.00	16,120.00
	strength not less than 425mmN/mm2 ,to BS 4466: cut				
3.8	Y12 diameter bars for ring beams	150.60	KG	143.00	21,535.80
3.90	R6 diameter bars as links or as strups to ring beams	80.50	KG	109.20	8,790.60
	Supply and fix Sawn formwork in soft wood as described				
3.10	Sides of columns and ring beams with thick 200mm wide and 200mm high	250.00	m	325.00	81,250.00
	Total Carried to summary				**184,733.90**
4	**ELEMEN. N0 4 WALL FINISHINGS AND PAINTINGS**				
	Wall finishing				
4.1	13mm thick (1:4) lime /gypsum plaster to internal walls with to steel trowel	154	m^2	520.00	80,080.00
4.2	13mm thick (1:4) lime /gypsum plaster to external walls with to steel trowel	154	m^2	520.00	80,080.00
	Total carried out				**160,160.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price KSH**	**Total Amount KSH ()**
5	**ELEMENT N0: 5 ROOFING**				
	Supply and fix the following in treated softwood Sawn cypress on roof trusses , this to include fabrication				
5.1	Supply and constuct roof including truss members, galvanised iron sheets gauge 28 complete with nails, straps and secured with iron bars embedded into tie beam. The truss members, common rafters, gusset plates, struts, purlins and ceiling joists are in hard wood and of the following section:	40	m2	2340.00	93,600.00
	Total carried to summary				**93,600.00**

6	**ELEMENT N0 6 CEILINGS :**				
6.1	provide ceiling board cypress 4mm thick brandering at 50x50mm thick cypress brandering at 600mm to center centers both sides	40	m^2	520.00	20,800.00
	Total carried forward to summary page				**20,800.00**
7	**ELEMENT N0 : 7.FLOOR FINISHINGS**				
7.1	Cement and sand (1:4) screeds and paving on concrete 40mm thick steel troweled screed with red oxide pigment incase is proposed	40	m^2	780.00	31,200.00
	Total carried forward to summary page		`		**31,200.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price KSH**	**Total Amount KSH ()**
8	**ELEMENT NO 8 PAINTING AND DECORATIONS**				
8.1	Prepare surface and paint one undercoat and two coats of emulsion paints on internal walls	154	m^2	260.00	40,040.00
8.2	Prepare and apply two coats of white cream emulsion paint, soffits of chipboard ceilings	40	m^2	520.00	20,800.00
8.3	prepare surface and paint one undercoat and two coats of emulsion paints on external walls	154	m^2	260.00	40,040.00
8.4	Apply two coats of paint on fascia board	42	m^2	325.00	13,650.00
	Total carried forward to summary page				**114,530.00**

9	**ELEMENT NO: 9 DOORS AND WINDOWS**				
	50mmx100mm wide timber boarding with tougned and				
9.1	Supply 900mmx2100mm high hard wood framed 1 1/4 " thick flush paneled door sashes with a 100x50mm soft wood timber frame, 3 pairs of hinges ,two number of 150mm barrel bolts .the outside barrel bolt to be lockable with pack lock .the should be painted in three coats of clear furnish	4	pcs	13000.00	52,000.00
9.2	Supply and install 700mm x 2100mm high steel door in 38mm x 25mm x 3mm thick RHS framing, and 3mm thick sheet plate, 3 pairs of heavy quantity brass oxidized hinges, two number 150mm barrel bolts and a 264 " tri-circle" or equal approved padlock with a set 3 original keys. The door to be painted in 3 coats of gloss paint.	1	pcs	7800.00	7,800.00
9.3	Supply and fix metal windows in metal frames, complete with shutters, fittings and wire mesh - Window size 1500x2000mm .	2	pcs	7,800.00	
9.4	Supply and fix metal windows in metal frames, complete with shutters, fittings and wire mesh - Window size 800x1200mm .	2	pcs	3,900.00	7,800.00
9.5	Supply and install 500mm wide and 500mm high steel grill with mosquito screen for latrines	4	pcs	3900.00	15,600.00
	Total carried forward to summary page				**83,200.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price KSH**	**Total Amount KSH ()**
10	**ELEMENT N0: 10. ELECTRICAL INSTALLATION**				
	Supply the electrical wiring ,english type to approval including fixing, connecting, cutting holes,chasings, conduiting and making good all finishes;				
10.1	Allow sum for wiring, conduiting,chasing and good making to all finishes,connection and test to the whole building to be approved starndrads	1	Item	32500.0	32,500.00
10.2	control panel box complete with main switch and seperatio for the lighting and socket power system	1	Nr	7800.00	7,800.00
10.3	Meter box including the provison of main switch and cut outs at the meter box	1	Nr	6500.00	6,500.00
10.4	one way one gang switch	3	Nr	1300.00	3,900.00
10.5	Sockets	5	Nr	1040.00	5,200.00
10.6	Two gang switch	3	Nr	1040.00	3,120.00
10.7	flourscent fitting 4ft complete with lamp	5	Nr	1300.00	6,500.00
	Total carried forward to summary page				**65,520.00**

11	ELEMENT No. 11: PLUMBING AND SANITARY				
	INSTALLATION				
	including all joints to services, overflow soil and waste				
11.1	fittings in the toilet and gulley traps from WC,up to	1	Item	45500.00	45,500.00
11.2	Supply and fix 600 x 450 x 5mm thick polished plate glass mirror with holes for domex screws and fixing to the wall above the wash hand basin	2	Nr	3900.00	7,800.00
11.3	Supply and fix white vitreous british or equivalent pedestal type water closet , squatting type, with a 10 liters low level flushing cisten complete with all fittings	2	Nr	19500.00	39,000.00
11.4	Supply and fix white vitreous british or equivalent sink size 300x200mm to the WC including all piping and connections	4	Nr	9750.00	39,000.00
11.5	Providing and fixing towel rail 600mm long complete with brackets fixed to wooden cleats with brass screws with concealed fittings arangement of approved quality colour	4	Nr	2600.00	10,400.00
11.6	Recessed toilet roll holder	4	Nr	1300.00	5,200.00
11.7	Supply and fix 100mm diameter heavy gauge PVC pipes to the toilets	4	Nr	9750.00	39,000.00
11.8	Allow for testing the whole of the sanitary installation during the progress of the works and again on completion and leave in perfect working condition	1	Item	13000.00	13,000.00
	Total carried forward to summary page				**198,900.00**
	GRAND TOTAL COST FOR Building			KES 1,444,404.26	

No	DESCRIPTION	QUANTITY	UNIT	Unit Price USD $	Total Amount USD ($)
Construction of Generator room for Immigration HQ					
	Element No: 1.SUBSTRUCTURE				
1.0	**Substructure**				
1.1	Clearance site including grubbing up all bushes and remove vegetable top soil and remove all debris from the site	12.00	m²	65.00	780.00
1.2	Excavate for strip foundation trenches 600mm wide and 500mm deep commencing at the oversite level and cart away to spoil as directed by the engineer	4.20	m³	1300.00	5460
1.3	Excavate for column pad footings size 400 x 400mm commencing at oversite level and not exceeding 600mm and carting away to spoil as directed by the site supervisor	0.512	m3	1,300.00	665.6
1.3	Return ,fill and ramp selected excavated materials around foundation in 150mm deep layers	1.68	m³	1300.00	2,184.00
	Supply vibrated plain concrete class 15/20 with crushed aggregates as described;				
1.4	In blinding 50mm thick at bottom of the foundation	0.56	m³	16250.00	9,100.00
	Supply vibrated plain concrete class 20/20 with crushed aggregates as described;				
1.5	In column footing and columns	1.15	m³	14300.00	16,473.60
	strength not less than 425mmN/mm2 ,to BS 4466: cut ,bent, and fixed including all necessary binding wire				
1.6	Y10mm diameter bars in strip footing	50.00	KG	143.00	7,150.00
1.7	R6 Diameter bars in strip footing as links	35.00	KG	109.20	3,822.00
1.8	Y10mm diameter bars in column footing	75.00	KG	143.00	10,725.00
1.9	Y12mm diameter bars in starter bars	50.00	KG	143.00	7,150.00
1.10	R6 Diameter bars as links in column	121.00	KG	109.20	13,213.20
1.11	Y12mm diameter bars in foundation walls	100.00	KG	143.00	14,300.00
	Total carried to summary				**91,023.40**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price USD $**	**Total Amount USD ($)**
2	**ELEMENT NO.2 REINFORCED FLOOR**				
	Hardcore				
2.1	200mm hardcore thick bed of quarry stones or equivalent materials, well compacted and blinded with fine aggregate to receive aggregates	2.40	m^3	1950.00	4,680.00
	Supply vibrated plain concrete class 20/20 with crushed aggregates as described;				
2.2	Concrete floor 100mm thick	1.20	m^3	14300.00	17,160.00
	wood as described				

2.3	150mm high to edges of concrete floor slab	28.00	m	325.00	9,100.00
	Damp proof course				
2.4	Provide and receive 1000g polythene sheeting on top of murram blinding including 100mm laps	12.00	m^2	390.00	4,680.00
2.5	A98 Mesh to ground floor slab including 100mm laps	12.00	m^2	390.00	4,680.00
	Total carried to summary				**40,300.00**
3	**ELEMENT No: 3 WALLING**				
3.1	**Supply cement sand blocks prepared in 1:3 sand ratio**				
3.2	200mm thick cement/sand blocks for external and internal walls	49.00	m^2	2340.00	114,660.00
3.3	**Cast in-situ vibrated reinforced concrete mix (1:2:4) crushed aggregate as described**				
	High yield steel reinforcement bars, characteristic strength not less than 425mmN/mm2 ,to BS 4466: cut				
3.5	Y10diameter bars for ring beams	100.00	KG	143.00	14,300.00
3.6	R6 diameter bars as links or as strups to ring beams	30.00	KG	109.20	3,276.00
	Total carried to next page				**132,236.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price USD $**	**Total Amount USD ($)**
	described				
3.7	Sides of columns and foundation beams 200mm-300mm	39.80	m^2	812.50	32,337.50
	Cast in-situ vibrated reinforced concrete mix (1:2:4) crushed aggregate as described				
3.8	the walls	0.80	m^3	14300.00	11,440.00
	strength not less than 425mmN/mm2 ,to BS 4466: cut				
3.9	Y12 diameter bars for ring beams	150.00	KG	143.00	21,450.00
3.10	R6 diameter bars as links or as strups to ring beams	75.00	KG	109.20	8,190.00
	Supply and fix Sawn formwork in soft wood as described				
3.11	Sides of columns and ring beams with thick 200mm wide and 200mm high	120.00	m	325.00	39,000.00
	Total Carried to summary				**112,417.50**
4	**ELEMEN. N0 4 WALL FINISHINGS AND PAINTINGS**				

	Wall finishing				
4.1	13mm thick (1:4) lime /gypsum plaster to internal walls with to steel trowel	49	m^2	780.00	38,220.00
4.2	13mm thick (1:4) lime /gypsum plaster to external walls with to steel trowel	49	m^2	780.00	38,220.00
	Total carried out				**76,440.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price USD $**	**Total Amount USD ($)**
5	**ELEMENT N0: 5 ROOFING**				
	Supply and fix the following in treated softwood Sawn cypress on roof trusses , this to include fabrication				
5.1	Supply and constuct roof including truss members, galvanised iron sheets gauge 28 complete with nails, straps and secured with iron bars embedded into tie beam. The truss members, common rafters, gusset plates, struts, purlins and ceiling joists are in hard wood and of the following section:	12	m2	2470.00	29,640.00
	Total carried to summary				**29,640.00**
6	**ELEMENT N0 6 CEILINGS :**				
6.1	provide ceiling board cypress 4mm thick brandering at 50x50mm thick cypress brandering at 600mm to center centers both sides	12	m^2	520.00	6,240.00
	Total carried forward to summary page				**6,240.00**
7	**ELEMENT N0 : 7.FLOOR FINISHINGS**				
7.1	Cement and sand (1:4) screeds and paving on concrete 40mm thick steel troweled screed with red oxide pigment incase is proposed	12	m^2	780.00	9,360.00
	Total carried forward to summary page		`		**9,360.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price USD $**	**Total Amount USD ($)**
8	**ELEMENT NO 8 PAINTING AND DECORATIONS**				
8.1	Prepare surface and paint one undercoat and two coats of emulsion paints on internal walls	49	m^2	325.00	15,925.00
8.2	Prepare and apply two coats of white cream emulsion paint, soffits of chipboard ceilings	12	m^2	520.00	6,240.00
8.3	prepare surface and paint one undercoat and two coats of emulsion paints on external walls	49	m^2	325.00	15,925.00
8.5	Apply two coats of paint on fascia board	15	m^2	325.00	4,875.00
	Total carried forward to summary page				**38,090.00**

9	**ELEMENT NO: 9 DOORS AND WINDOWS**				
	50mmx100mm wide timber boarding with tougned				
9.2	Supply and install 700mm x 2100mm high steel door in 38mm x 25mm x 3mm thick RHS framing, and 3mm thick sheet plate, 3 pairs of heavy quantity brass oxidized hinges, two number 150mm barrel bolts and a 264 " tri-circle" or equal approved padlock with a set 3 original keys. The door to be painted in 3 coats of gloss paint.	1	pcs	7800.00	7,800.00
	Supply and fix metal windows in metal frames, complete with shutters, fittings and wire mesh - Window size 1500x2000mm .	1	pcs	7,800.00	60.00
9.3	Supply and install 500mm wide and 500mm high steel grill with mosquito screen for latrines	2	pcs	3900.00	7,800.00
	Total carried forward to summary page				**15,660.00**
No	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Unit Price USD $**	**Total Amount USD ($)**
10	**ELEMENT N0: 10. ELECTRICAL INSTALLATION**				
	Supply the electrical wiring ,english type to approval including fixing, connecting, cutting holes,chasings, conduiting and making good all finishes;				
10.1	Allow sum for wiring, conduiting,chasing and good making to all finishes,connection and test to the whole building to be approved starndrads	1	Item	13000.0	13,000.00
10.2	control panel box complete with main switch and seperatio for the lighting and socket power system	1	Nr	7800.00	7,800.00
10.3	Meter box including the provison of main switch and cut outs at the meter box	1	Nr	6500.00	6,500.00
10.4	one way one gang switch	3	Nr	1300.00	3,900.00
10.5	Sockets	2	Nr	1040.00	2,080.00
10.6	Two gang switch	2	Nr	1040.00	2,080.00
10.7	flourscent fitting 4ft complete with lamp	1	Nr	1300.00	1,300.00
	Total carried forward to summary page				**36,660.00**
	TOTAL COST FOR GENERATOR ROOM				**588,066.90**

BILL OF QUANTITIES - of immigration HQ- GAROWE		BILL NO. GRAND SUMMARY		PAGE NO. 1/40
ITEM:	**DESCRIPTION:**	**QTY**	**RATE (USD)**	**TOTAL (USD)**
1	MAIN BUILDING			34,402,347.72
2	SEPTIC TANK/ DRAINAGE WORK			639,977.00
3	VISA AND PASSPORT OFFICES			1,584,912.55
4	BOUNDRY WALL			4,998,828.38
5	GUARD ROOM			1,444,404.26
6	GENERATOR ROOM			588,066.90
	Total Amount of the construction			**43,658,536.81**